प्रेसनोट

पोलीस अधीक्षक सिंधुदुर्ग, सिंधुदुर्गनगरी (दूरध्वनी क्रमांक ०२३६२-२२८६१४) यांजकडून सिंधुदुर्ग पोलीस घटकामधील पोलीस अधीक्षक कार्यालय व पोलीस ठाण्यांसाठी खुर्च्या, टेबल, कपाटे, रॅक, रायफल स्टँड वगैरे कार्यालयीन फर्नीचर व वस्तुंच्या खरेदीसाठी नमुद अटी शर्तीना अनूसरुन नोंदणीकृत फर्नीचर दुकानदार/पुरवठादार/कंपनी/फर्म यांच्याकडून दिनांक २८/०५/२०१८ रोजी पासून दिनांक ऑनलाईन टक्केवारीच्या दराच्या ई-निविदा मागविणेत येत आहेत.

| अ.क्र | तपशिल | दिनांक | वेळ |
|-------|---|------------|-------|
| 9 | ર | 3 | 8 |
| 1 | ई निविदा प्रसिध्द कालावधी | २८/०५/२०१८ | 90.00 |
| 2 | ई निविदा विक्री व सादर करण्यास सुरुवात दिनांक | २८/०५/२०१८ | 99.00 |
| 3 | ई निविदा पूर्व बैठक | ०१/०६/२०१८ | 90.30 |
| 4 | ई निविदा सादर करण्याचा अंतीम दिनांक | ०७/०६/२०१८ | 90.00 |
| 5 | ई निविदा उघडण्याची तारीख व वेळ | ०८/०६/२०१८ | 99.00 |

सर्व इच्छुक मक्तेदारांनी/ पुरवठादारांनी https://mahatenders.gov.in या संकेतस्थळावर आपल्या निविदा सादर कराव्यात. तसेच सदर ई-निविदे संदर्भातील माहिती सिंधुदुर्ग पोलीस दलाच्या www.sindhudurgpolice.gov.in या संकेतस्थळावर प्रसिध्द करण्यात आलेली आहे.

| 31 | STAINLESS STEEL DUST BIN | Nos |
|----|--------------------------|-----|
| 32 | FLOOR MATS | Nos |
| 33 | WALL CLOCK | Nos |
| 34 | PICTURE FRAME | Nos |
| 35 | NEWS PAPARE RACKS | Nos |
| 36 | MAGAZINE RACKS | NoS |
| 37 | Filing Tray | Nos |
| 38 | Name Plate for table | Nos |
| 39 | Dustbin | Nos |
| 40 | Dustbin | Nos |

निविदेचे वेळापत्रक

| अ.क्र | तपशिल | दिनांक | वेळ |
|-------|---|------------|-------|
| 9 | 2 | 3 | 8 |
| 1 | ई निविदा प्रसिध्द कालावधी | २८/०५/२०१८ | 90.00 |
| 2 | ई निविदा विक्री व सादर करण्यास सुरुवात दिनांक | २८/०५/२०१८ | 90.00 |
| 3 | ई निविदा पूर्व बैठक | ०१/०६/२०१८ | 90.30 |
| 4 | ई निविदा सादर करण्याचा अंतीम दिनांक | ०७/०६/२०१८ | 90.00 |
| 5 | ई निविदा उघडण्याची तारीख व वेळ | ०८/०६/२०१८ | 99.00 |

- १.संपूर्ण निविदा प्रक्रिया ऑनलाईन पध्दतीने राबविण्यात येईल. निविदे संबंधी सर्व सूचना व अटी शर्ती https://mahatenders.gov.in या संकेत स्थळावर प्रसिध्द करण्यात आलेल्या आहेत.
- २.निविदे करिता आवश्यक सर्व कागदपत्रांची माहिती वरील संकेत स्थळावर उपलब्ध असेल व सर्व संबंधीतांनी https://mahatenders.gov.in या संकेतस्थळावर निवीदा भराव्यात.
- ३. सदर निविदे करिता निविदा फॉर्म फी १००००/- व बयाणा रक्कम १०००००/- रुपये राहील.
- ३.प्राप्त निविदा कोणतीही करणे न देता नाकारणे अथवा स्वीकारण्याचे अधिकार पोलीस अधीक्षक सिंधुदुर्ग यांनी राखून ठेवलेले आहेत.
- ४.निविदेतील अटी व शर्ती निविदाधारकास बंधनकारक राहतील.

(दिक्षीत गेडाम) पोलीस अधीक्षक, सिंधुदुर्ग

अटी व शर्ती

- 9.निविदा सुपूर्द करताना खालील गोष्टींचा अंतर्भाव असणे अनिवार्य राहील. निवीदा फॉर्म फी व इसारा फी (EMD) (बयाणा रक्कम) ही वर नमुद संकेतस्थळावर दर्शविलेलेल्या नुसार NET Banking द्वार भरणा करावयाची आहे. निविदा फी व इसारा रक्कम Net Banking द्वारे रकमा भरणा केल्या बाबतचे विहीत नुमुन्यातील प्रमाणपत्र तांत्रीक लिफाफ्या सोबत आपलोड करावायाचा आहे.
- २. मक्तेदराने सादर केलेल दर हे निविदा उघडल्याच्या दिनांका पासून ३६० दिवसापर्यंत बंधनकारक राहतील.
- ३. कोणतीही एक अगर सर्व निवीदा कोणतेही करण न देता मंजूर अथवा नामंजुर करण्याचा अधिकार पोलीस अधीक्षक, सिंधुदुर्ग यांनी राखुन ठेवलेला आहे.
- ४. मक्तेदार यांनी दर हे B.O.Q. फॉर्म मध्ये ऑनलाईन सादर करावयचे आहे.
- ५. मक्तेदार याचे नोंदणीकृत फर्नीचर दुकान असणे अगर तो नोंदणीकृत फर्नीचर पुरवठादार असणे आवश्यक आहे.
- ६. निविदा नामंजूर झाल्यास त्या संबंधात कोणताही पत्रव्यवहार केला जाणार नाही.
- ७.निवीदा मंजूर झाल्याचे कळविल्यावर करारपत्र व इतर कागदपत्र ठरवून दिलेल्या मुदतीत पूर्ण न केल्यास बयाणा रक्कम जप्त करण्यात येईल.
- ८. प्रसिध्द केलेले कोणतेही काम निविदा सूचीतुन वगळण्यात येईल. तसेच शुध्दीपत्रक प्रसिध्द करण्यात येईल. त्याबाबत कोणताही खुलासा मागता येणार नाही.
- ९. निविदा मजकुरात रकमेत वा अथवा अन्य कोणत्याही बाबतीत बदल झाल्यास तसे शुध्दीपत्रक प्रसिध्द करण्यात येईल. त्याकरीता निवीदा भरावयाच्या अंतीम वेळे पर्यंत तशी शहानिशा संबंधीतांनी करायची आहे.
- 90. उपरोक्त मजकुरात अथवा रकमेत बदल संभवू शकतो. ऑनलाईन प्रसिध्दी मजकुर तसेच रक्कम अंतीम राहील.
- 99. निवीदा फॉर्मसोबत मक्तेदारास / पूरवठादारास सिंधुदुर्ग पोलीस दलास सेवा दिल्याचे अथवा वस्तुंचा पूरवठा केल्याचे प्रमाणपत्र Work Experience Certificate सादर करणे आवश्यक आहे.
- १२.उपरोक्त कामाच्या देयकाची रक्कम ही प्रशासकीय मान्यता देण्यात आलेल्या रकमेस अधीन राहून अदा केली जाणार आहे.
- 9३.वस्तुंचा पूरवठा केल्या नंतर पुढील ५ वर्षांपर्यंत वस्तुची देखभाल दुरुस्ती मक्तेदाराने अथवा पुरवठादाराने करणे आवश्यक आहे.
- १४. सदर ई-निविदे संदर्भात वेळोवेळी पोलीस अधीक्षक, सिंधुदुर्ग यांनी दिलेल्या निदेशांचे पालन करावे लागेल.
- 9५. सदर निविदे संदर्भांत कोणताही वाद निर्माण झाल्यास त्यावर निर्णय घेण्याचा अधिकार पोलीस अधीक्षक, सिंधुदुर्ग यांचा राहील.
- १६.जर दोन किंवा अधिक पूरवाठादारांनी निविदेमध्ये दिलेले दर सारखेच असतील तर प्राप्त निविदेपैकी कोणतीही ईनिविदा स्वीकारण्याचा अथवा नाकारण्याचा अधिकार पोलीस अधीक्षक सिंधुदुर्ग यांना राहील.
- 90 वरील अर्टी व शर्तीमध्ये फेरबदल करण्याचा तसेच काही नवीन अटी व शर्ती समाविष्ट अथवा शिथील ाकरण्याचा तसेच कोणतेही करण न देता एकतर्फी निविदा मंजुर करण्याचा व करारनामा संपूष्टात आणण्याचा अधिकार पोलीस अधीक्षक, सिंधुदुर्ग यांनी राखून ठेवलेला आहे. तो निविदा धारकास बंधनकारक असेल. काही वाद निमार्ण झाल्यास पोलीस अधीक्षक, सिंधुदुर्ग यांचा निर्णय अंतीम राहील.
- १८. सदर निविदेसंदर्भात निवीदाधारक मा. न्यायालयात गेल्यास त्याची कार्यकक्षा ही सिंधुदुर्ग जिल्हा असेल.
- 9९.निविदा धारकाने करारनाम्यातील कोणत्याही अटींचा भंग केल्यास त्याची पूर्ण अनामत रकम जप्त करण्यात येईल.
- २०.कार्यालयीन वापरासाठी असलेल्या खूर्च्यांचा पूरवठा पोलीस अधीक्षक, कार्यालय सिंधुदुर्ग येथे करावा लागेल. आदेशामधील वस्तुंची संख्या कमी किंवा जास्त होण्याची शक्यता आहे.
- २१. निवीदा पोलीस अधीक्षक, कार्यालय सिंधुदुर्ग येथील पोलीस उपअधीक्षक, मुख्या. यांच्या दालनात दिनांक ०८/०६/२०१८ रोजी सकाळी ११.०० वाजता उघडण्यात येईल.

- २२.निविदा वैधतेचा कालावधी ६० -३६० दिवसांचा आहे.
- २३. निविदा प्रक्रियेतील बयाणा रक्कम व निविदा शुल्क ऑनलाईन भरण्यात यावेत.
- २४. वरील अटी व शर्ती मान्य असल्यास इच्छुक मक्तेदारांनी ई-निविदा सादर करावी.
- २५.निवीदेमध्ये नमुद केले साहीत्य हे १५ दिवसांच्या आत या कार्यालयास पूरविणे बंधनकारक आहे.
- २६.निविदेमध्ये देण्यात आलेले दर हे एका वर्षासाठी लागु राहतील तसेच सदर ई-निवीदा मंजूर झाल्यानंतर साहित्याच्या आवश्यकतेप्रमाणे पुरवठादारास पुरवठा आदेश देण्यात येतील. त्यानुसार साहित्याचा निर्देशीत ठिकाणी वेळोवेळी पुरवठा करणे बंधनकारक आहे. पूरवठा आदेश देण्याबाबतचे अधीकार पोलीस अधीक्षक, सिंधुदुर्ग यांनी राखून ठेवलेले आहे.
- २७.महाराष्ट्र राज्य शासन निर्णय क्रमांक भांखस-२०१४/प्र.क्र.८२/भाग-III/उद्योग-४ दि. ०१/डिसेंबर २०१६मध्ये नमुद सर्व बाबी निविदा धारकांना व यशस्वी निविदाधारकांना लागू राहतील.
- २८. निविदे संदर्भात कोणतीही समस्या असल्यास ०२३६२-२२८६१४ या कार्यालयीन दूरध्वनीवर संपर्क करावा.

स्थळ : सिंधुदुर्गनगरी, दिनांक: २६/०५/२०१८

पोलीस अधीक्षक, सिंधुदुर्ग

Requirement Of Product

| No | Name Of Product | Description | Unit |
|----|---|--|------|
| 1 | EXECUTIVE TABLE WITH SIDE TABLE | Providing and making on site the TABLE and installing in position main table in PI CABIN & BOARD ROOM of size 2400mm(L)X900mm(W)X750mm(H) with top made up of 19 mm thick Marine BWP (boiling water proof) thick exterior grade prelaminated BWP PLY BORD and having superior edge profile supported on Gable ends/sides made out of 25mm thick prelamPLY boards with 2mm thick PVC edge banding. Modesty panels in 19mm thk prelam PLY board. Gable ends & modesty exposed edges are in 2 mm thick PVC edge banding & sealed edges are in 0.8 mm thick PVC edge banding. Wire routing/ wire management shall be provided on main table or side table as specified. Table should have independent MS powder coated CPU trolley, wire manager and MS powder coated key board tray of standard size. The keyboard tray to accommodate mouse pad. The side table of size 900mm(L)X500mm(W)X750mm(H)made up 25 mm thick prelam BWP PLY board top supported with storage cabinet below in 19mm thick prelam PLY board & back of the unit made up of 9 mm PLY board with 75 mm thick skirting. Two equal size shutters and one shelf in centre made up of 18 mm thickPLY e board with 2 mm thick PVC edge banding fixed with s.s. brush finish brass hinges & 4" s.s 304 grade brush finish handles, premium lock with wave key technology to be provided. The pedestal unit of size 480mm(L)X640mm(W)X550mm(H), Top made up of 25 mm thick prelaminated PLY board & sides in 19 mm prelaminated PLY board and 75 mm thick skirting with 2mm thick PVC edge banding & sealed edges are in 0.8 mm thick PVC edge banding Three equal size drawers with front fascia having central locking system with roller slide mechanism and casters for added mobility. All material shall be of approved make. All works complete as per the drawing / indicative image, technical specification and as directed by the engineer/ architect .note- 1mm laminet to be fhinish in outer area | Nos. |
| 2 | SHO TABLE WITH SIDE TABLE | Providing and making on site the TABLE in DEPT./ STAFF of size 2100mm(L)X800mm(W)X750mm(H) with top made up o of 19 mm thick Marine BWP (boiling water proof) mm thick exterior grade prelaminated board and having superior edge profile supported on Gable ends/sides made out of 25mm thick prelam bwp ply boards with 2mm thick PVC edge banding. Modesty panels in 18mm thk prelam BWP PLY board. Gable ends & modesty exposed edges are in 2 mm thick PVC edge banding & sealed edges are in 0.8 mm thick PVC edge banding. Wire routing/ wire management shall be provided on main table or side table as specified. Table should have independent MS powder coated CPU trolley, wire manager and MS powder coated key board tray of standard size. The keyboard tray to accommodate mouse pad. The side table of size made up 25 mm thick prelam BWP PLY board top supported with storage cabinet below in 18mm thick prelam BWP PLY board & back of the unit made up of 9 mm PLY board with 75 mm thick skirting. Two equal size shutters made up of 18 mm thick prelamPLY board with 2 mm thick PVC edge banding fixed with s.s. brush finish brass hinges & 4" s.s 304 grade brush finish handles, premium lock with wave key technology to be provided. All material shall be of approved make. All works complete as per the drawing / indicative image, technical specification and as directed by the engineer/ architect. | Nos |
| 3 | ACCOUNTANTS / PASSPORT /OFFICERS /TABLE | Providing and making on site the TABLE in DEPT./ STAFF of size 1500mm(L)X600mm(W)X750mm(H) with top made up o of 19 mm thick Marine BWP (boiling water proof) mm thick exterior grade prelaminated board and having superior edge profile supported on Gable ends/sides made out of 25mm thick prelam bwp ply boards with 2mm thick PVC edge banding. Modesty panels in 18mm thk prelam BWP PLY board. Gable ends & modesty | Nos |

| 4 | COMPUTER TABLE WITH LOW HEIGHT SOLID PARTITION& BOTH SIDE GLASS PARTITION | exposed edges are in 2 mm thick PVC edge banding & sealed edges are in 0.8 mm thick PVC edge banding. Wire routing/ wire management shall be provided on main table or side table as specified. Table should have independent MS powder coated CPU trolley, wire manager and MS powder coated key board tray of standard size. The keyboard tray to accommodate mouse pad. key technology to be provided. All material shall be of approved make. All works complete as per the drawing / indicative image, technical specification and as directed by the engineer/ architect. Providing, fabricating and fixing in position Panel based modular workstations in STAFF ROOM which Includes Partition, work surface, pedestal & MS powder coated CPU trolley and MS powder coated key board tray of standard size. The keyboard tray to accommodate mouse pad. Work surface size 900 mm(L) X 600 mm(W) X 750 mm(HT) & gable ends will be in 25mm thick exterior grade prelaminated Particle board with 2mm thk PVC imported edge banding tape for tops & 0.8mm thk PVC imported edge binding tape for verticals. The bottom surface of the table shall also be laminated. The worktops will be supported by MS powder coated brackets at regular intervals. The worktops | Nos |
|---|---|---|-----|
| | | shall be provided with PVC wire manager for cabling. Front Partition size 600 mm(L) X 400 mm(HT) and the thickness will be 60mm with the inside gap between two tiles will be approximately 50mm for higher wire carrying capacity. | |
| 5 | TABLE FOR STAGE | Providing & fixing stage table of Size- 2400mm(L) x 750mm(W) x750mm(HT) in 19 mm Marine BWP (boiling water proof) plywood with 19 mm top & front fascia finished with approved shade 1 mm laminate externally and 0.8mm thk laminate internally, table to have 75 mm skirting. Table to have cutouts for wire management with necessary labour, placing in position etc. complete. All material shall be of approved make. All works complete as per the drawing, technical specification and as directed by the engineer/ architect.(DWG CODE:WP1-WP12 in DRAWING NO - IWAS-1001 | Nos |
| 6 | MAIN CHAIR For OFFICERS | Supplying and placing in position armed revolving high back chair for PI of approved make and colour, BIFMA (The Business & Institutional furniture manufactures association) compliant with features like front pivot synchro tilt mechanism having seat & back tilt option,5 position locking with anti shock back mechanism & seat depth adjustment, PU Armrests, branded leatherite for Seat and Back, Die Cast Aluminium Base with buffing finish & nylon twin Castors as per approved indicative image and make etc. Rate shall include of all iron mongeries hardware, fittings, fixtures etc. All material shall be of approved make. All works complete as per the drawing/ indicative image, technical specification and as directed by the engineer/ architect. | Nos |
| 7 | SECOND OFFICER CHAIR | Supplying and placing in position armed revolving medium back chair in DEPT., STAFF RM, DISCUSION RM, of approved make and colour with HR (high-resilience) foam seat and back BIFMA (The Business & Institutional furniture manufactures association) compliant and having features like knee tilt syncronous mechanism with 4 position locking & anti shock feature. PU adjustable Armrests, nylon base with PU castors. The back and seat upholstered in fabric. Rate shall include of all iron mongeries hardware, fittings, fixtures etc. All material shall be of approved make. All works complete as per the drawing/ indicative image, technical specification and as directed by the engineer/ architect | Nos |
| 8 | CHAIRS FOR STAFF | Supplying and placing in specified position armed revolving medium back chair of approved make, model, colour and finish including BIFMA (The Business & Institutional furniture manufactures association) compliant and having features like HR foam seat and back, syncro 1 tilt mechanism withlocking facility & anti shock feature ,PU coated adjustable Armrests, class 3 DIN Gas lift, Die Cast Aluminium / nylon Base with Nylon castors as per approved image and make etc.Rate shall include of all iron mongeries hardware, fittings, fixtures etc. All | Nos |

| | 1 | T | 1 |
|----|--------------------------|--|------|
| | | material shall be of approved make. All works complete as per the drawing/ Image, technical specification and direction of the Engineer. (Please refer annexure for approved make / manufacturer). | |
| 9 | CHAIR FOR VISITORS | Supplying and placing in specified position armed fixed medium back visitor chair of approved make, model colour and finish including BIFMA (The Business & Institutional furniture manufactures association) compliant and having features like fixed base, armrest Fixed Poly Propeylene, Base MS Tubular-4legged Stackable with HR foam , powder coated, back and seat with fabric upholstery, waterfall edge design for long seating and specially designed curvy understructure for enhanced strength and stability. Rate shall include of all iron mongeries hardware, fittings, fixtures etc. All material shall be of approved make. All works complete as per the drawing/ Image, technical specification and direction of the Engineer. (Please refer annexure for approved make / manufacturer). | Nos |
| 10 | SOFA 3 SEATERS | Supplying & placing in position sofa in PI CABIN & BOARD ROOM having solid frame structure made with pneumatic nails supported by plywood, inner frame made with chemical treated approved wood. Back rest to have a layer of approved make polyester of 180gsm over foam seats to avoid wrinkle less and to provide soft feel on upholstery seating. Cushion to have 75mm elastic webbing of 350gsm used on the frame with diagonal pattern to distribute stress evenly. Upholstery cover made with good quality leatherite stitched with nylon bonded thread providing lasting strength etc complete. The legs shall be of s.s 304 grade tubular section of dia 75mm and 2 mm thickness with rubber gasket. All material shall be of approved make. All works complete as per the drawing/ indicative image, technical specification and as directed by the engineer/ architect.(Seat Height - 410 mm) | Nos. |
| 11 | 3 SEATER BENCH- STEEL | Providing and placing in position approved make stainless steel grade 304, 3 Seater Bench -SILVER (2100 L x800 ht x 600 w). All the materials shall be of approved make. All works complete as per the drawing, indicative image, specification and as directed by the engineer/ architect | Nos |
| 12 | STORAGE RACK | Supplying and installing in position back storage of size 900mm(L)X600mm(W)X2100mm(H) Top made up of 25 mm thick prelaminated particle board & having frame and covering panels made up of 18mm thick exterior grade pre laminated particle board, back of the unit made up of 9 mm particle board with 75 mm thick skirting. Two equal size shutters and one shelf in centre made up of 18 mm thick prelam particle board with 2 mm thick PVC edge banding fixed with s.s. brush finish brass hinges & 4" s.s 304 grade brush finish handles, premium lock with wave key technology to be provided. All material shall be of approved make. All complete as per the drawing / indicative image, technical specification and as directed by the engineer/ architect. | Nos |
| 13 | LIBRARY BOOKS STORAGE | Supplying and Installing in position Metal Rack of size as mentioned below with four glass shutters, metal parts to have a Epoxy Polyester Powder coat finish within the range of 50 microns DFT (Dry film thickness). The Carcass & Shelves to be made out of CRCA(Cold rolled close annealed) Sheet not less than 0.8mm thick, storage top has Metal Top Panel & Each compartment has a storage shelf, should have a load carrying capacity of 80kg(UDL-Uniformly distributed load). (Each rack size - 914mm (L)X320mm (W)X330mm(HT). Each Door has 3 mm Thk transparent glass for clear inside vision secured in a Metal frame through rubber gasket, has a Scissor mechanism for receding inside the top of respective compartment & ensures parallel & smooth movement. Each Door | Nos |

| | | has 6 Lever Cam lock with common key & Plastic side end caps as Handle which is easy to grip. All material shall be of approved make. All works complete as per the drawing/ indicative image, technical specification and as | |
|----|-------------------------------|---|-------------|
| 14 | Filing CABINETS | directed by the engineer/ architect. of custom made size to fill space left after placing the ready cabinets ,providing and making on site the storage of approved make, colour and size custom made. with 19 mm thick Marine BWP (boiling water proof) plywood with 25 mm thickness louvered sandwich shutters in 12mm thick BWP (boiling water proof) plywood framework with 6mm thick BWP (boling water proof) plywood on both sides fixed on SS. brush finished brass 'L' hinges & 100 mm height SS 304 grade handles and having the louvers in 38x6mm thick wooden lipping. The cabinet to have 19mm thick plywood shelves fixed on shelf buttons, back sheet in 8mm plywood & finished with 3mm thick veneer with 3 coats or more of melamine polish externally and 0.8mm thick laminate internally. All exposed edges to be finished with teak wood lipping with 3 coats or more of melamine polish to match the shade of veneer & with necessary labour, S.S brush finish hardware, cleaning, placing in position etc. complete. All material shall be of approved make. All works complete as per the drawing, specification and as directed by the engineer/ architect. (Refer drawing number -IWAS1015). | Sq. Mtr. |
| 15 | METAL SHELVING RACK | Providing and fabricating rack of size 121cm x 50cm x 195cm. The main structure shall be made of 35mm x35mm x1.2mm s.s. square tube with five shelves out of 18 swg GI .MS The four legs shall be fixed with nylon adjustable feet as per specification All work complete as per approved specification, in GI MS ISI and architects drawings / indicative image. | Nos |
| 16 | WEAPONS /RIFLE RACK | Providing and fabricating plate rack of size 120cm x 50cm x 195cm. The main structure shall be made of 35mm x35mm x1.2mm s.s. square tube with five shelves out of perforated 18 swg. GI MS plate. The four legs shall be fixed with nylon adjustable feet as per specification All work complete as per approved specification, in s.s.304 and architects drawings / indicative image. | Nos |
| 17 | RD | Supplying and Installing in position of locker modules of size (SIZE: 900 mm(L)X 600mm(W) X 2100mm (HT) with 4 Doors in each unit made out of CRCA (Cold rolled close annealed) Sheet not less than 0.8mm thick for Carcass & Shelves. Skirting to be done with 1.2mm thick CRCA (Cold rolled close annealed) Sheet. Storage Top to be made out of 2mm thick CRCA (Cold rolled close annealed) Sheet and Shelves with Stiffener to have an overall thickness not less than 15mm. The shelves should have a load carrying capacity of 35kg(UDL-Uniformly distributed load). All metal parts to have a Epoxy Polyester Powder coat finish within the range of 50 microns DFT (Dry film thickness) complete as directed by the Engineer. (each module will have 3 units with 4 compartments of lockers. Size of each locker 300mm(L) x 600mm(W) x 475mm(HT). (Total 12 nos of lockers in each module.) Each unit has 4 shutters. Each locker have 12 Lever cam lock with lock lever & ABS plastic handle. All material shall be of approved make. All works complete as per the drawing/ indicative image, technical specification and as directed by the engineer/ architect. | Nos |
| 18 | SHOE RACK FOR LABS | Providing and fixing shoe rack internally in 19 mm thick Marine BWP (boiling water proof) ply and 8 mm thick ply back and with 2 shelves fixed in inclined position (Total 3 nos of compartments) with teak wood lipping finished with 1 mm laminate. Exposed edges of ply to be finished with 19x6mm teak wood lipping with 3 coats or more of melamine finish. Backing to be finished with french polish with necessary labour and hardware etc. All material shall be of approved make. All works complete as per the drawing, specification and as directed by the engineer/architect. | Nos |
| 19 | FALSE CEILING Modular Type | Gypliner or equivalent ceiling which includes providing & fixing G.I. HG angle of sie 0.55 mm thick having two equal flanges of 25 mm each screw fixed to | Sq. Mtr |

| | T | | T |
|----|--|--|------------|
| | | brick wall / partition with the help of nylon sleeves & screws at 610 mm c/c. Then suspending chan 12.5 mm tapered edge Gypboard (confirming to IS:2095-1982) is then fixed to channel section with 25 mm drywall screws at 230 mm centre. Screw fixing is done mechanically with drill machine and suitable attachment. Finally square and tapered edges joints of the boards are jointed and finished so as to have flush look which includes filling finishing with jointing compound, joint paper tape and two coats of Drywall top coat suitable for Gypboard (as per recomended practices of India Gypsum Limited). | |
| 20 | CARPET/PVC Venal | Provising and installing tuffed carpet flooring made from wool or man made fibres or their blends. The jute carpet backing fabric as per (IS 4900 part 1-3: 1984) or any other suitable equivalent backing mateirial. Blend composition of pile yarn, pile density, pile thickness, colour fastness, moth resistance should satisfy IS standards for carpet flooring IS 5884:1993. The sample to be approved before installation from the architect. | Sq. Mtr |
| 21 | VERTICAL BLINDS | Providing & fixing in position vertical blinds 100 mm wide. The fabric should be 100% cotton fibres. The fabric should be chemically treated for falame retardant. The weight of fabric should be 777 grams per 15 meter and of approved colour with head rail of 25mm height and 47mm wide extruded high strength anodised aluminium alloy section. End control unit state of art reduction ratio of 3:5:1 for a very smooth operation of the blind. It shall include all necessary fittings and fixtures like Tilt rod, Tilter chain , Carrier/ Runner, spacer, installation bracket, cord weight, cord, bottom mechanism consisting of weight and chain etc. complete. All material shall be of approved make. All works complete as per the drawing, technical specification and as directed by the engineer/ architect. | Sq. Mtr |
| 22 | MIRROR PANELLING (3x6 Feet) | Providing and fixing 12 mm BWP plywood backing on wall fixed with screws in line & level and fixing 6mm mirror with silicon sealant on 12 mm plywood back with plain polish on all edges of mirror, skirting of 75mm at the bottom shall be finished with 1 mm thick laminate with all necessary hardware, fittings, etc. All material shall be of approved make. All works complete as per the drawing, specification and as directed by the engineer/architect. | Nos |
| 23 | PIN - UP BOARDS (SOFT BOARDS) | Supply and installing in position soft display board having aluminum frame including 12mm thick soft board with blazer cloth top fixed in frame with clip fitting with all stainless steel hardwares and easy fixing to the wall. All material shall be of approved make. All works complete as per the drawing / indicative image, specification and as directed by the engineer/ architect | Nos |
| 24 | NOTICE BOARD | Providing and fixing in position Notice board of size 1200mm(L) X 900(HT) mm made of Aluminium frame with Acrylic shutter including 12mm thick soft board with blazer cloth top fixed in frame with clip fitting with all stainless steel hardwares such as screws, locking arrangement etc. and making arrangement for fixing on wall all complete as per design. All material shall be of approved make. All works complete as per the drawing./ indicative image, specification and as directed by | Nos |

| | | the engineer/ architect. | |
|----------|------------|---|-----|
| 25 | | Providing and fixing in position approved Ceramic white matt finish marker board of (SIZE - 2200 X 1200) having Moulded | |
| | | Anodized Aluminium frame with Eraser Complete of approved | |
| | | make including all accessories. All works complete as per the | Nos |
| | WHITE | drawing./ indicative image, specification and as directed by the | |
| | MARKER | engineer/ architect | |
| | BOARD | | |
| 26 | GREEN | Providing and fixing in position non magnetic green chalk board | |
| | CHALK | of Ceramic steel sheet matt finish in green colour including | |
| | BOARD | Anodized Aluminium frame Virgin ABS Moulded 300x100mm | |
| | | chalk tray & Eraser complete. Including all accessories complete. | Nos |
| | | All the materials shall be of approved make. All works complete | |
| | | as per the drawing./ indicative image, specification and as | |
| | | directed by the engineer/ architect.SIZE : 900mm (L) x 1200mm | |
| 27 | | (HT) Providing and fixing in position flat signages made from 3 mm | |
| 4 | | thick Aluminium composite panel. vinyl pasted on it with letters | |
| | | cut out. The panel will then be fixed on the door with 3M VHB | |
| | | tape/ SS. stud of size 25mm diameter) screw arrangement as | Nos |
| | | required. All material shall be of approved make. All works | |
| | INTERNAL | complete as per the drawing, specification and as directed by the | |
| | SIGNAGES | engineer/ architect. SIZE - 150mm (L) X 150mm (HT) | |
| 28 | | Providing and fixing in position flat signages made from 3 mm | |
| | | thick Aluminium composite panel. vinyl pasted on it with letters | |
| | | cut out. The panel will then be fixed on the door with 3M VHB | |
| | | tape/ SS. stud of size 25mm diameter) screw arrangement as | Nos |
| | | required. All material shall be of approved make. All works | |
| | INTERNAL | complete as per the drawing, specification and as directed by the | |
| | SIGNAGES | engineer/ architect. SIZE - 300mm (L) X 150mm (HT) | |
| 29 | | Providing and fixing in position flat signages made from 3 mm | |
| | | thick Aluminium composite panel. vinyl pasted on it with letters | |
| | | cut out. The panel will then be fixed on the door with 3M VHB | Na |
| | | tape/ SS. stud of size 25mm diameter) screw arrangement as | Nos |
| | INTERNAL | required. All material shall be of approved make. All works complete as per the drawing, specification and as directed by the | |
| | SIGNAGES | engineer/ architect. SIZE - 400mm (L) X 150mm (HT) | |
| 30 | JIGINAGES | Providing and fixing in position flat signages made from 3 mm | |
| - • | | thick Aluminium composite panel. vinyl pasted on it with letters | |
| | | cut out. The panel will then be fixed on the door with 3M VHB | |
| | | tape/ SS. stud of size 25mm diameter) screw arrangement as | Nos |
| | | required. All material shall be of approved make. All works | |
| | INTERNAL | complete as per the drawing, specification and as directed by the | |
| | SIGNAGES | engineer/ architect. SIZE - 600mm (L) X 900mm (HT) | |
| 31 | STAINLESS | Providing and placing in position approved make stainless steel | |
| | STEEL DUST | grade 304 cylindrical dustbin with cover (300 dia x 600 ht) . All the | |
| | BIN | materials shall be of approved make. All works complete as per | Nos |
| | | the drawing, indicative image, specification and as directed by | |
| | | the engineer/ architect | |

| 32 | FLOOR MATS | Providing and placing in position PVC green mat of approved make, approved colour made of special polymer tufts that scrape stubborn dirt with designer anti-curl edge guards, natural elastomer base,100% anti skid, hygienic & non-toxic etc. All the materials shall be of approved make. All works complete as per the drawing, specification and as directed by the engineer/architect (SIZE - 1000mm(L) X 600mm(HT) | Nos |
|----|-------------------------|--|-----|
| 33 | WALL CLOCK | Supply and fixing in position approved make, approved colour wall clock circular or square (min one side 300mm) quartz with bold numbers, 3 hands. All the materials shall be of approved make. All works complete as per the drawing, specification and as directed by the engineer/ architect | Nos |
| 34 | PICTURE FRAME | Supplying & fixing in position approved canvas painting with synthetic frame & lamination. The details need to be as per the instructions of Engineer. All the materials shall be of approved make. All works complete as per the drawing, specification and as directed by the engineer/ architect. (SIZE - 900mm(L) x 600mm(HT) | Nos |
| 35 | NEWS PAPARE RACKS | Supplying and installing in position Newspaper rack of size 900 x 600 mm made from CRCA (Cold rolled close annealed) Sheets with 20 SWG (standard wire gauge) and Processed with Oven baked painting process with 3 in 1 Anti-Corrosion Chemical treatment for strong corrosion resistant and Durabity. Reading Top shall be of exterior grade prelam particle board. All the materials shall be of approved make. All works complete as per the drawing / indicative image, specification and as directed by the engineer/ architect. | Nos |
| 36 | MAGAZINE RACKS | Supplying and installing in position Magazine racks of size 900mm(W) x 450mm(D) x 1830mm(H) having rigid knock down construction & made from CRCA (Cold rolled close annealed) steel sheet panels of 0.6mm thickness & front frame of 0.8mm thickness finished with Epoxy polyester powder coating of 50microns thickness(+/-10) with leveler for height adjustment of 5mm maximum. There will be 5 level racks (each rack size - 900mm(W) x 450mm(D) x 355mm(HT) & each of 5 level shall have a storage shelf behind. The metal display trays shall be fixed at an angle for easy viewing and have a receding facillity to access storage behind. Plastic rollers will be provided for sliding. The uniformly distributed load capacity of each shelf shall be 80kg maximum. All the materials shall be of approved make. All works complete as per the drawing / indicative image, specification and as directed by the engineer/ architect. | Nos |
| 37 | Filing Tray | Size 14 X 18 Inch Vergin Plastic Base Standerd filing Tray In Duel colour | Nos |
| 38 | Name Plate for table | Acralic base moduler type tranfarent name plate | Nos |
| | + | | |
| 39 | Dustbin | Cylendercal type 15 Inch hight Stanless steel material | Nos |